

## **SAPULPA, TIMBER RIDGE ESTATES EAST CONCRETE PANEL REPLACEMENT SPECIFICATIONS**

The City of Sapulpa, OK. is seeking sealed bid proposals for concrete panel replacement in the subdivision of Timber Ridge Estates East in Sapulpa. Streets included are Meadowside Ln., Hillwood Dr., Glenside Ln., Greendale, and Webb Dr. The total concrete panel replacement is estimated at 62,486sqft. City staff will cut, remove existing concrete panels, and prepare a new aggregate base.

Contract will be required to purchase and install cages, at 10' intervals, drill and install 3/4" inch epoxy coated dowels every 12" inches into adjoining concrete pavement and remaining gutter line and pour and finish 6" of concrete where each panel has been removed and prepared. 6" B.C.C. ODOT SPEC 414

Control joints are not to exceed the width of the lane and all joints will require backer rod and sealed with approved sealant.

Centerline will require 3/4" expansion joints and start and stop of dig outs will have expansion joints. There will be an expansion joint installed every 100' feet if dig out length exceeds 100' feet.

Traffic will always remain open.

Concrete specifications and a map of the area can be found at the City of Sapulpa website at [www.sapulpaok.gov](http://www.sapulpaok.gov). open Quicklinks in the upper right corner and select Bid Opportunities.